

Hydraulic Engineering

NLWKN GB II „Planing and Construction“

Henning Paulsen-Jacobs, Mike Stöter

Expert advice: hydraulics und hydrochemistry

NLWKN GB III „Water body and river basin management “

Dirk Post, Dieter de Vries, Andreas Engels

Masterplan Ems 2050

Tidal polder Coldemüntje
Restoration of tidal wetlands

Climate adaptation in deltas II: Wetland restoration

28. June 2023



Tidal area of the Ems today - issues



- **Slit problem (fluid mud)**
- and low water quality



Canalisation


- Deepening
- Straightening
- > Large tidal range, with pronounced flood current
- Dykes and summer dykes
- Bank enforcements

Master Plan Ems 2050?

Tidal area of the Ems in a **bad status** (Natura 2000, WFD)

EC infringement procedure

Avoid?!



Administration,
conservation associations,
largest company relying on
the waterway


Objectives of the Masterplan Ems 2050 (Ecology and economy):

1. Resolving the slit problem
2. Improving water quality
3. **Improving estuary habitats (5 km²+x)**
4. Protecting (Grass)birds and their habitats (2 km²)
5. Maintaining the Ems as an efficient federal waterway

Financing:

Federal state Lower Saxony and Federal republic Germany

Ems and tidal polder Coldemüntje



Historic development of the Ems and the flow loop near Coldemüntje

[Ostfriesische Landschaft 2015,
Preussische Landesaufnahme 1898]



1939 [Archiv Rubach u. Partner], 1962, 2015 [LGLN]


Action plan

Passage structure,
sedimentation basin,
overflow threshold with weir flap
to **reduce entry of sediments**
in order to prevent fast siltation
(to be completed 2024)

Tidal system
(tidal creek, mudflats,
wetland)
(to be completed 2023)

Freshwater pond
(compensation)
with irrigation pump
(to be completed 2023)

Costs ~13.5 Mio €



Challenges



Unanimity among contractual partners


Area procurement (only if owners are willing to sell, not represented in the contract):

- obtain the area and clear compensation obligations
 - where to put the excavated soil?
 - > two tries needed to obtain the **permit**



Engineering structures

- resolving the slit problem
 - ensuring dyke safety
 - keeping it „simple“ for operation and entertainment



Challenges



Earthwork

- Planning: Diversity of the types of soil and the concept of further use
- Building: **Clay soil** (processability in the construction area, difficulties improving nearby grassland)



Public relation

- **Acceptance** and information, time horizon 2050





Still constructing

**Thank you very much for your
Attention!**

Any Questions?